



1 DUE DILIGENCE PHASE

~1 WEEK

- Gather home comparables for project guidance
- Order survey (if missing)

2 HIRING PHASE

1–2 WEEKS · INTERVIEWS CONDUCTED IN ORDER

1. **ARCHITECT** interviews
 2. **BUILDER** interviews
 3. **DESIGNER** interviews (if applicable)
 4. **LANDSCAPE ARCHITECT** interviews (if applicable)
- Decision on build team finalized before Design Phase begins.

3 DESIGN PHASE

1–3 MONTHS · ITERATIVE PLAN DEVELOPMENT

- Initial team meeting — introductions
- 1:1 with Builder — budget building
- 1:1 with Architect — wishlist & initial plans
- 1:1 with Designer — initial finishes & mood board
- Design Meeting #2 — initial plans review, corrections, budget alignment, sizing
- Second pass of plans — designer on call for fine tuning
- Design Finishes Meeting — major selections, budget
- Walk Your Plans — finishes, layout & functionality
- Third pass of plans — exterior finishes, ceiling heights, flow
- Additional passes scheduled as needed
- Final Plans Set
- Mood Board Finalized — major selections penciled in

4 PRE-CONSTRUCTION

WEEKS PRECEDING GROUNDBREAKING

- Demo permit pulled (if applicable)
- Plans submitted to codes
- Building permits pulled

5 CONSTRUCTION

~12-MONTH BUILD SEQUENCE · BROAD-SCOPE MILESTONES

1. **SITE PREP** — site cleared, utilities marked
2. **FOUNDATION** — excavation, footings, foundation walls, waterproofing, backfill, first major inspection
3. **FRAMING & DRY-IN** — wall framing, floor systems, roof, windows & exterior doors installed; weather-tight shell
4. **MEP ROUGH-INS & INSPECTIONS** — mechanical, electrical, plumbing routed & inspected; fireplaces set
5. **INSULATION, DRYWALL & INTERIOR FINISHES BEGIN** — insulation, drywall, trim, doors, stairs, cabinetry staged
6. **CABINETRY, FIXTURES, FLOORING & LANDSCAPE** — cabinets, countertops, tile, hardwood, paint finish, fixtures, appliances, hardscape
7. **PUNCH-LIST, CO & MOVE-IN** — final inspections, Certificate of Occupancy, walkthroughs, punch items, keys delivered

THROUGHOUT THE PROJECT

ONGOING TOUCHPOINTS

DESIGNER CHECK-INS

BI-WEEKLY DURING
CONSTRUCTION

Designer walks the site with TSC and the builder to confirm finish placement, verify material staging, and resolve field questions before they become change orders.

MONTHLY BUDGET REVIEWS

FIRST WEEK OF EACH MONTH

A single sit-down each month covering draw activity to date, projected spend for the coming 30 days, variance against contracted allowances, and any recommended reallocations.

UPCOMING SELECTION MEETINGS

SCHEDULED 4–6 WEEKS AHEAD

Selections are calendared before they are needed on site — plumbing, lighting, appliances, cabinetry hardware, tile, and specialty items — so lead times never delay the build.

SUBCONTRACTOR QUOTE REVIEWS

AS BIDS COME IN

Every subcontractor quote is checked against industry-standard pricing for materials and labor. When a bid is out of line, TSC presents alternative subcontractor options.

OUR COMMITMENT

All communication with your architect, designer, builder, and tradespeople funnels through TSC — one point of contact from Day 1 through Certificate of Occupancy so your interests are protected and decisions are made with full information.